



KENYA URBAN ROADS AUTHORITY

Efficient and safe urban roads

Barabara Plaza, Mazao Road - Off South Airport Road, JKIA

Tel: 254-020-8013844 / 254-717-105233

Email: info@kura.go.ke Web: www.kura.go.ke

P.O. Box 41727-00100, GPO, NAIROBI

Ref No. KURA/EO/SCM/27/Vol.3 (249)

Date: 6th April, 2020

ALL BIDDERS

RE: UPGRADING OF ROADS IN MERU COUNTY HEADQUARTER

TENDER No.: KURA/DEV/HQ/302/2019-2020

ADDENDUM 1

Reference is made to the above subject matter;

This is to notify all bidders that an addendum has been issued for the above tender.

S/NO	AMENDMENT	ACTION
1	Location and Extent of Site	Replace with the attachment page 2
2	Bill 16	Replace with the attachment page 3
3	Bill 21	Replace with the attachment page 4

Please note that, the Tender Opening/Closing still remains the same date of 28th April, 2020 at 10.00 am.


Saadia Hajj Adankhalif
FOR: DIRECTOR GENERAL

101 SPECIAL SPECIFICATION

SECTION 1 – GENERAL

102 LOCATION AND EXTENT OF SITE

The works comprise *UPGRADING OF ROADS IN MERU COUNTY HEADQUARTERS along Imenti Forest Edge*. The project roads traverse through existing earth roads and are approximately 13km in length. They are a total of 10 roads and each of their length are as tabulated in the table below.

No.	Start	End	Length (KM)
1	Eastern Bypass (at the junction of Hospital road and Kaaga road)	Kaithe Junction on Meru Maua road(C91)	5.6
2	Starts at Hospital road opp. Consolata girls secondary school	Terminates on B6 next to mosque	0.6
3	Starts at ch 0+300 on road 3A and passes thru cathedral church	Terminates at Hospital road	0.45
4	Museum	library	0.5
5	Starts at Cocacola on Mwandantu road and branches at YMCA/PCEA	Terminates at Marvins Manyatta, Just at the back entrance of county offices	0.7
6	Down Town Filling station meru-Mikinduri Road	Terminates at Angaine Plaza, (Matatu stage) and Gakoromone fresh produce market.	0.45
7	Starts at B6(Meru-Nanyuki) at MSS Petrol station	Terminates on junction behind veterinary offices	0.7
8	Starts at Kinoru Kenya Power substation next to MEWAS water storage tank	Terminates at junction with western Bypass at the Imenti Forest Edge	0.7
9	B6 at Gitimbini – Irinda- Giantune	Western bypass	2.5
10	Meru maua(Mwithumwiru)	Kaaga (Eastern bypass) link	0.8
Total			13.0

BILL No.21 : MISCELLANEOUS BRIDGE WORKS					
ITEM	DESCRIPTION	UNIT	QTY	RATE (KSHS)	AMOUNT
21.01	Provide and apply bituminous waterproof to abutments and wingwalls in two layers at a rate of 0.55L/m ² as shown in the drawings or as directed by the Engineer.	m ²	2,000.00		
21.03	Provide and place steel flexibeam guard-rails to bridge approaches including steel post, anchors and welding as directed by the Engineer.	m	200.00		
21.04	Provide and place approved elastomeric bridge bearings of dimension shown in the drawings.	No.	14.00		
21.07	As item 21.06 but handrail posts 75 x 75 x 4mm RHS	no	20		
21.13	75mm diameter to abutments and wing walls drain pipes	M	80		
Total Bill 21 Taken To Summary page					

 3