



## KENYA URBAN ROADS AUTHORITY

*Efficient and safe urban roads*

Barabara Plaza, Mazao Road - Off South Airport Road, JKIA

Tel: 254-020-8013844 / 254-717-105233

Email: [info@kura.go.ke](mailto:info@kura.go.ke) Web: [www.kura.go.ke](http://www.kura.go.ke)

P.O. Box 41727-00100, GPO, NAIROBI

Ref. No. KURA/EO/SCM/3Vol.30 (51)

Date: 13th May 2022

TO ALL BIDDERS

RE: ADDENDUM 1

SUBJECT: REHABILITATION OF GARDEN ESTATE ROADS

Reference is made to the above subject.

You're hereby advised to replace the below Bill of quantities with the revised Bill items as attached.

| CORRECT TENDER NO AS IT SHOULD APPEAR IN THE COVER PAGE ( attached) | TENDER NAME                           | CORRECTION                                            |
|---------------------------------------------------------------------|---------------------------------------|-------------------------------------------------------|
| KURA/RMLF/HQ/361/2020-2022                                          | Rehabilitation of Garden Estate Roads | Page 20, BOQ, Bill No. 11 & 12-Add missing quantities |

We also clarify that the required Tender Security is of Kshs.200, 000.00.

Please note that the tender Opening Date/Closing remain the same as per the Tender Notice

Saadia Haji Adankhalif  
Deputy Director, Supply Chain Management  
FOR: DIRECTOR GENERAL

| BILL 11: SHOULDER TO PAVEMENT              |                                                                                                                                                                                                                   |                |     |              |        |    |
|--------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-----|--------------|--------|----|
| ITEM                                       | DESCRIPTION                                                                                                                                                                                                       | UNIT           | QTY | RATE<br>KSHS | AMOUNT |    |
|                                            |                                                                                                                                                                                                                   |                |     |              | SHS    | CT |
|                                            | Note: All haulage is to be included in the Contractor's rates and prices. There is no separate payment for overhaul                                                                                               |                |     |              |        |    |
| 11.01                                      | Prepare surface of existing shoulders, accesses and busbays, including benching where necessary, waterprocess and compact in accordance with the specification and as directed by the Engineer to receive gravel. | M <sup>2</sup> | 150 |              |        |    |
| 11.02                                      | Provide, place and compact natural gravel to shoulders, accesses and busbays as directed by the Engineer.                                                                                                         | M <sup>3</sup> | 80  |              |        |    |
|                                            | Total of Bill Carried Forward to Summary                                                                                                                                                                          |                |     |              |        |    |
| BILL 12: NATURAL MATERIAL BASE AND SUBBASE |                                                                                                                                                                                                                   |                |     |              |        |    |
| ITEM                                       | DESCRIPTION                                                                                                                                                                                                       | UNIT           | QTY | RATE<br>KSHS | AMOUNT |    |
|                                            |                                                                                                                                                                                                                   |                |     |              | SHS    | CT |
|                                            | Note: All haulage is to be included in the Contractor's rates and prices. There is no separate payment for overhaul                                                                                               |                |     |              |        |    |
| 12.01                                      | Provide, place and compact natural gravel or approved quarry waste material in layers of 150mm to form subbase layer for carriageway and accesses                                                                 | M <sup>3</sup> | 720 |              |        |    |
| 12.03                                      | Provide, lay, and compact hand packed stone material including filling of voids with stone dust and watering as directed by the Engineer.                                                                         | M <sup>3</sup> | 460 |              |        |    |
|                                            | Total of Bill Carried Forward to Summary                                                                                                                                                                          |                |     |              |        |    |

Issued by the Kenya Urban Roads Authority –MAY, 2022